

PRESIDENCY UNIVERSITY

OFFICE OF THE PLANNING AND DEVELOPMENT

Name of the Work:- Providing aluminium sliding window in seminar room of Hindi department at N.S. building 3rd floor, Presidency University, 86/1, College Street, Kolkata-700 073.

Estimate No:- C-04/2016-17

Sl No	Items of work	Qty.	Unit	Rate	Amount
1	Taking out heavy iron grated door or window (jail pattern or existing) with locking arrangement after cutting out from walls and refixing the same including mending all damages.[Mending charges to be paid separately] PWD-sch./Civil [Page no- 81, Item no-32]	13	Sqm	230.00	2,990.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] PWD-sch./Civil [Page no- 151, Item no-2]				
	(i) With 1:6 cement mortar (b) 20 mm thick plaster	7	Sqm	181.00	1,267.00
3	Supplying, fitting & fixing in proper position of aluminium sliding window is required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Anodized for fabrication of composit 2 or 3-track sliding window, of basic sections of any ISI embossed / certified make and brand with 4mm coloured or plane Glass with other ancillary fittings fitted & fixed with necessary material etc. complete in all respect as per direction of Engineer - In-Charge. (B) 15 Micron colour anodizing. I) Natural white Sliding window 2or 3-track	13	Sqm	6,450.00	83,850.00

Total Cost= ₹88,107.00

Say, ₹88,107.00

Rupees eighty-eight thousand one hundred and seven only.

I/We agree to carry out the work mentioned in the General Summary at par*/.....%

(..... percent) above */ % (..... percent) below*
the rates shown in the specified estimate.

Signature of the Tenderer

*Please cross whichever is not applicable